

WAINGAWA RIVER MANAGEMENT SCHEME

OCTOBER 2000 FLOOD DAMAGE SCHEDULE

Site	Damage	Repair Works	Cost (\$)	Priority
Wouters	300 m of severe bank erosion and stopbank damage – course change threat through downstream farmland	Channel alignment, bank battering, and stopbank restoration	\$20,000	High
Johnson/Minnell	Severe bank erosion over 300 m length threatening farmland	Channel alignment, gravel groynes, & bank battering	\$10,000	High
Bridges reach	Bank erosion threatening stopbanks, industrial land, and SH2 Bridge	Channel alignment & bank battering	\$3,000	Medium
Tulloch/Bark Yard	100 m bank erosion	Channel alignment & gravel groynes	\$10,000	Low
Total			\$43,000	